

Construction Management

Demolition

Heavy Construction

Site Preparation

Emergency Response

Underground Utilities

Transportation



## Lake Cataouatche, Pump Station 1 & 2

Phase 1 Temporary Floodwall Reinforcement and Levee Enlargement  
Jefferson Parish, LA

**Owner:** U.S. Army Corps of Engineers

**Contract Number:** W912P8-06-D-0087, Task Order 0005

**Approximate Contract Value:** \$5,100,000

**Actual Completion Date:** July 2008

**Completion Time:** 150 Calendar Days

**Point of Contact:** Lary Yorke-U.S. Army Corps of Engineers

Cycle received the 2008 Merit Gold Award from Associated Builders and Contractors, Inc. for this project.

This contract included:

- Clearing and Grubbing
- Degrading of existing levee-9,000 cy
- Excavation and relocation of existing drainage canal-22,000 cy
- Concrete scour protection-2,300 sf
- Levee construction-40,000 cy
- Rip Rap armor stone protection-2,000 tons
- Installation of 45,000 sf of steel sheet piling
- Relocation of pump station discharge piping
- Installation of a temporary bridge
- Installation of 500 lf of 72" CMP temporary culverts
- Installation of 500 lf of 72" CMP permanent culverts
- Closure of existing canal
- Demolition of Existing Floodwall