

Construction Management

Demolition

Heavy Construction

Site Preparation

Emergency Response

Underground Utilities

Transportation



WBV-60 Westwego Floodwall

Interim Phase I Floodwall Reinforcement Jefferson Parish, LA 8(a) MATOC

Owner: U.S. Army Corps of Engineers/Southern Services

Contract Number: W912P8-06-D-0099, Task Order 0002

Approximate Contract Value: \$7,000,000

Completion Date: October 2008

Point of Contact: Mark Nunez-Southern Services and Equipment, Inc.

Cycle Construction performed as a subcontractor to Southern Services for this project.

This contract included:

- Ground improvements consisting of 2,958 columns (80ft deep x 36" diameter) utilizing deep soil mixing technology
- Construction of a temporary retaining structure for gas utility modifications
- Installation of 10,500 sf of sheet pile
- Installation of 21,000 cy of embankment
- Installation of rip rap embankment
- Installation of stone slush grout scour protection